

ADDRESS

Coty Price 410-804-3851

Estimate 505358

DATE 03/24/2025

EXPIRATION DATE 04/24/2025

SALES REP

Bob Ries

PHONE NUMBER

410-382-3373

PROPERTY MANAGER

Coty Price 410-804-3851

PROJECT	QTY	AMOUNT	
Job location Sussex Square Condominiums 8323 Norwood Dr Millersville, MD			
Project	1	153,722.00	
Mill & Pave Excavate 2 grass islands 18x4 removing approximately 6inches of grass/ dirt to reach parking lot grade once we are at grade another 4 inches of dirt & stone will be removed to install 4inches of 19mm base asphalt prior to the mill and pave Mill approximately 68,321sq ft of damaged asphalt to a depth of 2 inches clean up and haul away all debris Apply CRS-2 tack coat at a rate of .05 to .10 gallons per square			

Install 2inches of 9.5mm surface course asphalt machine laid followed by two 5-ton asphalt rollers for a true and firm finish Set up and re-stripe as previously as defined

Liberty Asphalt requires 1/3 deposit prior to commencement of work and remaining balance due upon completion of work. Any unpaid balance over 30 days from work completion as dated on invoice is subjected to 2% interest per month. In case of default, collection fees and/or legal fees and any additional cost associated with collection will be added under the Fair Debt Protection Practice Act. If full payment is not received within 60 days from final invoice date, warranty rights will be waived.

Liberty Asphalt LLC Will guarantee 1 year warranty for materials and labor

Thank You!

yard

TOTAL \$153,722.00

Accepted By

Accepted Date

P.O Box 565 Glen Burnie MD. 21060 Service@libertyasphalt.net 410.382.3308



ADDRESS

Coty Price 410-804-3851

Estimate 505360

DATE 03/24/2025

EXPIRATION DATE 04/24/2025

SALES REP Josh Lefaivre **PHONE NUMBER** 443.848.2114

PROPERTY MANAGER Coty Price 410-804-3851

PROJECT	QTY	AMOUNT
Job location Sussex Square Condominiums		
Project	1	15,975.00
Mill & Pave Pool Area Mill approximately 6,061sq ft of damaged asphalt to a depth of 2 inches clean up and haul away all debris Apply CRS-2 tack coat at a rate of .05 to .10 gallons per square		

yard

Install 2inches of 9.5mm surface course asphalt machine laid followed by two 5 ton asphalt rollers for a true and firm finish Set up and re-stripe as previously defined

Liberty Asphalt LLC Will guarantee 1 year warranty for materials and labor

Thank You!

\$15,975.00 TOTAL

Accepted By **Accepted Date**



ADDRESS

Coty Price 410-804-3851

Estimate 505368

DATE 03/25/2025

EXPIRATION DATE 04/25/2025

SALES REP

Josh Lefaivre

PROPERTY MANAGER

Coty Price 410-804-3851

PROJECT	QTY	AMOUNT
Job location Sussex Square Condominiums 578 Belmawr Pl Millersville, MD		
COURT TWO		
Project	1	67,450.00
Mill & Pave Mill approximately 29,964 sq ft of damaged asphalt to a depth of 2 inches. Clean up and haul away all debris. Apply CRS-2 tack coat at a rate of .05 to .10 gallons per square yard Install 2 inches of 9.5mm surface course asphalt machine-laid followed by two 5-ton asphalt rollers for a true and firm finish.		
Project	1	9,675.00
Job location Sussex Square Condominiums 578 Belmawr Pl Millersville, MD		
Excavate 2 damaged concrete dumpster pads to a depth of 6 to 8 inches and 3 Ada concrete ramp clean up and haul away all debris Form up where needed Add CR-6 stone where needed Install 360sq ft of #6 wire mesh Pour 4,000 psi concrete to a depth of 6 inches hand level with a broom finish.		
Project	1	21,664.00
Job location Sussex square condominiums 578 Belmawr Pl Millersville, MD		
Excavate 427LF of asphalt curbing that sits on top of the existing asphalt parking lot		

Excavate 427LF of asphalt curbing that sits on top of the existing asphalt parking lot Saw cut approximately 427LF of asphalt excavate saw cut area to a depth of 12inches to install a new header curb clean up and haul away all debris Form up 427LF of new concrete header curb

Pour 4,000psi concrete to a depth of 19 inches one foot below grade which will leave a 7 inches of curbing above grade

Thank You!

TOTAL \$98,789.00

Accepted By Accepted Date

Estimate 358 \$153,722
Estimate 360 \$ 15,975
Estimate 368 \$ 98,789

Total \$268,486