

JOB PROPOSAL

PREMIER POOL MANAGEMENT, INC.
12339 Carroll Ave., Suite B
Rockville, MD 20852

Estimate #	14548
Date Ordered	12/29/2025
Order Taken By	H
Start Date	7/28/2025
Comments	Main Pool Repairs

Customer Info
Sussex Square Condominium 8309 Norwood Drive Millersville, MD 21108

Item	Description	Qty	Unit Cost	Total
S101	Repair estimated 150 sqft of damaged hollowed plaster - Grind out hollow and damaged plaster - Remove all loose debris - Pour new plaster in effected areas *Note: After pool is drained an accurate sq footage will be provided.	1	4,500.00	4,500.00
C102	Replace coping stone. (each) Price includes: - Demo and disposal - Materials and installation - Perimeter caulking	11	185.00	2,035.00
S105	Repair damaged skimmer. Work will include: - Cleaning out the affected areas - Fill the cracks and patch them with an epoxy resin mixture that fully seals the skimmer bodies and has the same structural strength as the original material -Re-grout the skimmer parges	2	995.00	1,990.00

Warranty: 6 months from project completion.

Subtotal

Sales Tax (6.0%)

Total

Additional Notes:

- * Please do not pay from this proposal. Invoice to follow.
- * Job completion may be delayed due to parts availability.
- * Additional charges may apply.
- * Price valid for 30 days.

AUTHORIZED SIGNATURE _____

CUSTOMER NAME _____ DATE _____

Please do not pay off of this proposal, an invoice will be generated and sent under separate cover. Upon receipt of the invoice, payment must be made by the due date or invoice will incur a 5% late fee per month.
--

JOB PROPOSAL

PREMIER POOL MANAGEMENT, INC.
12339 Carroll Ave., Suite B
Rockville, MD 20852

Estimate #	14548
Date Ordered	12/29/2025
Order Taken By	H
Start Date	7/28/2025
Comments	Main Pool Repairs

Customer Info
Sussex Square Condominium 8309 Norwood Drive Millersville, MD 21108

Item	Description	Qty	Unit Cost	Total
S106	Re-purge damaged skimmers. Work will include: (each) - Removing coping stones above the skimmer (if necessary) - Repair skimmer well tiles - Re-grout skimmer purges - Reattach coping stone - Remove and dispose of all debris	2	365.00	730.00
S109b	Replace Eyeball return fitting	1	550.00	550.00
W212	Pool Deck Repair. Price includes: - Address up to 50 ft of deck cracks - Fill in with hydraulic crack resistant cement	1	1,250.00	1,250.00
S200	Replace rail anchor (set of 2)	1	765.00	765.00

Warranty: 6 months from project completion.

Subtotal	\$11,820.00
Sales Tax (6.0%)	\$0.00
Total	\$11,820.00

Additional Notes:

- * Please do not pay from this proposal. Invoice to follow.
- * Job completion may be delayed due to parts availability.
- * Additional charges may apply.
- * Price valid for 30 days.

AUTHORIZED SIGNATURE _____

CUSTOMER NAME _____ DATE _____

Please do not pay off of this proposal, an invoice will be generated and sent under separate cover. Upon receipt of the invoice, payment must be made by the due date or invoice will incur a 5% late fee per month.